

KARNES ELECTRIC COOPERATIVE, INC.

Main Office (830)780-3952

Pleasanton Office (830)569-5538

Date: 02-04-11

SINGLE PHASE OR THREE PHASES CT METERING TYPICAL INSTALLATION

COOPERATIVE FURNISHED, OWNED AND INSTALLED

- A. Pole to be Set Within 30' of Transformer Pole.
(max)
- B. Ground Rod and Ground Wire
- C. Service Wire
- D. CT Meter Base

MEMBER FURNISHED

- A. Shall Install Approved Disconnect Panel with Main Breaker According to Ampere Size Request by Electrician.
- B. Cooperative Will Install Connectors Furnished by Member.
- C. Disconnect Shall Be Grounded to Pole Ground.

