

KARNES ELECTRIC COOPERATIVE, INC.

Main Office (830)780-3952

Pleasanton Office (830)569-5538

Date: 02-04-11

METER ON HOUSE OR BUILDING THROUGH ROOF SERVICE NOT TO EXCEED 300 VOLTS

COOPERATIVE FURNISHED, OWNED AND INSTALLED

- A. Meter
- B. Meter Base to be Mounted 5' 6" Above Ground.
- C. 2" Galvanized Rigid Conduit with Weatherhead and Wire.
- D. Straps
- E. 1/2" Conduit for Ground
- F. Ground Rod and Ground Wire

**** EVERYTHING IS TO BE INSTALLED ON HOUSE BY ELECTRICIAN.**

MEMBER FURNISHED

- A. Breaker Panel with Main Breaker.
- B. Metallic Nipple, Hub and Locknuts.
- C. Bell Bushing Wire Protector in All Conduit Openings.
- D. Disconnect Shall Be Grounded to Ground Wire.

NOTE: 200 AMP SERVICE REQUIRES 2" CONDUIT & 3/0 COPPER WIRE.
125 AMP SERVICE REQUIRES 1 1/2" CONDUIT & 1/0 COPPER WIRE.

